



Studies on Genetic Variability in Ridge Gourd (*Luffa acutangula* L. Roxb.) under Prayagraj Agro-Climatic Condition

Anirudh Yadav ^{a*} and Devi Singh ^{a#}

^a Department of Horticulture, Naini Agricultural Institute, SHUATS, Prayagraj (U.P.), India.

Authors' contributions

This work was carried out in collaboration between both authors. Both authors read and approved the final manuscript.

Article Information

DOI: 10.9734/IJPSS/2022/v34i2231367

Open Peer Review History:

This journal follows the Advanced Open Peer Review policy. Identity of the Reviewers, Editor(s) and additional Reviewers, peer review comments, different versions of the manuscript, comments of the editors, etc are available here: <https://www.sdiarticle5.com/review-history/89913>

Original Research Article

Received 20 May 2022
Accepted 28 July 2022
Published 03 August 2022

ABSTRACT

Aim: To study the genetic variability of ridge gourd under Prayagraj Agro-climatic condition.
Study Design: Randomised Complete Block Design (RCBD).
Place and Duration of Study: Horticultural Research Farm, Department of Horticulture, Naini Agricultural Institute, SHUATS, Prayagraj. Between August 2021 to October 2021.
Methodology: 11 genotypes of fennel were sown in three replications in RCB design. In each replication data were observed on five plants and averaged for all 21 characters under study.
Results: Analysis of variance showed the presence of significant variation among different genotypes for all characters studied. Days to germination and plant height [30DAS] exhibited high estimates of GCV and PCV both. Genetic parameters revealed that high heritability (broad sense) was observed for fruit yield per hectare, plant height [30DAS], fruit length, plant height [60DAS], days to first harvest of fruits, days to germination, leaf length, sex ratio, fruit girth, fruit yield per plant, days to first male flowering, shelf life, leaf per plant [30DAS], Vitamin C content and number of primary branches per plant. Fruit yield per hectare, fruit yield per plant, fruit girth, fruit length, leaf length, plant height [60DAS], plant height [30DAS] and days to germination exhibited high heritability broad sense coupled with high values for genetic advance as percent of mean.

^oResearcher,

[#]Associate Professor;

*Corresponding author: E-mail: yadavanirudh100@gmail.com;

Conclusion: Selection in these traits will lead to higher efficiency in breeding programme for improving yield. Thus these traits may be ranked as most important attributing traits for seed yield per plant in fennel.

Keywords: Ridge gourd; GCV; PCV; heritability; genetic advance; path coefficient analysis.

1. INTRODUCTION

Ridge Gourd (*Luffa acutangula* Roxb.) is a creeping vine plant in the *Cucurbitaceae* family that bears usually cylindrical fruits, which are used as vegetables. Ridge gourd is a cross pollinated diploid crop which is grown in all the parts of India. Gelatinous compound in ridge gourd is 'Luffein'. Most favourable temperature for Ridge gourd is 18°C-28°C. Flower colour is pale yellow and anthesis time is morning hours. Botanically, Ridge gourd is known as *Luffa acutangula* Roxb. belongs to family *Cucurbitaceae*. It is a diploid cross-pollinated species with chromosome number $2n=2x=26$ [1]. Ridge gourd probably originated from India [2]. It is mainly cultivated in China, India, Turkey, Iran and other parts of south-east Asia. Progenitor of Ridge gourd is "*Luffa graveolens*."

The area under Ridge gourd production in India accounts to 10.03 thousand ha with production of 3.16 million tonnes in year 2018-19. The production of Ridge gourd in Uttar Pradesh is 427.81 tonnes for year 2018-19. The ridge gourd is used as cooked vegetable. It has many uses in ayurvedic medicines. According to 'Ayurvedic' medicines, the oil from its seed is good for the liver and the body. (Source: [3]). Ridge gourd has moisture 95.2 g, magnesium 11 mg, sodium 2.9 mg, Vitamin C 5 mg, 3.5g Carbohydrates, Oxalic acid 27 mg, Calcium 40 mg, Phosphorous 40 mg, Potassium 50 mg, Chlorine 7 mg and many other nutrients out of 100 g of edible portion (Nutritional Research Laboratory, Coonoor, Choudhary, 1967).

A proper understanding of classification of ridge gourd germplasm for qualitative and quantitative traits may serve as useful guidelines for plant breeders for selection and improvement of the crop. Germplasm serves as the basic material with a plant breeder to initiate any breeding programme. It consists of genetic variability for quantitative and qualitative traits. Genetic variability and their quantification for qualitative and quantitative characters of economic importance are prerequisite for any crop improvement programme. The knowledge of genetic advance and heritability guides the

breeder to select superior parents to initiate fruitful breeding programme. Thus, for any yield improvement programme superior parent possessing better heritability and genetic advance for various traits is essential [4].

2. MATERIALS AND METHODS

The experimental material for present investigation comprised of 11 genotypes of ridge gourd [*Luffa acutangula* (L.)] were obtained from the different sources (Table 2) and sown at Horticultural Research Farm, Department of Horticulture, Naini Agricultural Institute, Sam Higginbottom University of Agriculture, Technology and Sciences, Prayagraj. The experiment was conducted in Randomized Block Design comprising 11 (10 genotypes +1 check) genotypes with three replications during August-October 2021. The unit plot size was 2 m². The plants were planted with a spacing of 150 cm between the rows and 60 cm between the plants. The observations were recorded on randomly selected six plants on characters comprising Days to germination, Days to first male flowering, Days to first female flowering, Days to first harvest of fruits, Sex ratio (M:F), Plant height at 30 DAS (cm), Plant height at 60 DAS (cm), Leaf per plant 30 DAS, Leaf per plant 60 DAS, Number of primary branches per plant 60 DAS, Leaf length (cm), Leaf width (cm), Number of fruits per plant (Avg.), Fruit length (Avg.) (cm), Fruit girth (Avg.) (cm), Fruit weight (g), Fruit yield per plant (kg/plant), Fruit yield per hectare (t/ha), Number of seeds per fruit (Avg. of 5 fruits), Vitamin C content (mg/100gm), Shelf Life (in days).

Prayagraj falls in central plain sub-zone of Agro-climatic zone V (Source: *Perspective and Strategic Plan (SPSP) for IWMP* of Uttar Pradesh, Department Of Land Development and Water Resources, Government of U.P.). Naini is situated between the parallels of 20° 33' 40" to 21° 50' N latitude and 73° 27' 58' and 73° 56' 36' E longitude. The climate of this area is tropical characterized by fairly hot summer, moderately cold winter with humid and warm monsoon. The rainfall of this region is heavy and normally received from June to September. Most

of the precipitation is received through south-west advancing monsoon, concentrating in the months of July and August. The meteorological data for the cropping seasons are presented in Table 1.

Analysis of Variance was calculated using the formula suggested by Fisher and Yates, [5]

Coefficient of variation including Genotypic coefficient of Variation and Phenotypic Coefficient of Variation was calculated using the formula suggested by Burton, [6]; Heritability (broad sense) was calculated using the formula suggested by Allard, [7]; Genetic advance was calculated using the formula suggested by Johnson et al., [8].

Table 1. Meteorological data during experimental period (August-October, 2021)

Months	Week	Temperature ($^{\circ}$ C)		Relative Humidity (%)		Total rainfall (mm)
		Max.	Min.	Max.	Min.	
August – 2021	I	33.6	24.0	95.0	63.0	124.8
	II	34.8	24.0	100.0	62.0	141.6
	III	37.0	24.6	87.0	50.0	55.6
	IV	35.8	24.2	100.0	52.0	101.6
September – 2021	I	36.2	24.8	97.0	50.0	71.4
	II	34.4	24.2	87.0	55.0	5.6
	III	36.4	24.0	100.0	48.0	222.8
	IV	37.0	24.4	100.0	47.0	71.6
October -2021	I	34.6	24.2	93.0	52.0	10.8
	II	35.6	24.0	85.0	52.0	0
	III	35.8	24.2	92.0	52.0	11

Grand total rainfall (mm) = 816.8

Source: Agro-meteorological observatory Unit, School of Forestry and Environmental SHUATS, Prayagraj

Table 2. List of sources of genotypes

Sl. No	Genotypes list	Source
01	Jaipur long	Shankar seeds, Prayagraj, U.P.
02	Dharidar	Krishak hitashi seeds, Prayagraj, U.P.
03	Anamika	Right seeds, Prayagraj, U.P.
04	Sumitra	Ujjwal seeds, Prayagraj, U.P.
05	Latika	Ankur seeds, Nagpur, MH.
06	Riwaka	Winseed, Betul, M.P.
07	Aarti	VNR Seeds, C.G.
08	DS-4700	DSPL Seeds, Prayagraj, U.P.
09	Neha	Aadya Agricultures, Prayagraj, U.P.
10	Shamita	Sakata seeds, Indore, M.P.
11	Pusa Nasdar (Check)	VNR seeds, C.G.

Table 3. Analysis of variance (ANOVA) for 21 quantitative characters in ridge gourd

Characters	Mean sum of Squares		
	Replication (df=2)	Treatment/ Genotypes (df=10)	Error (df=20)
Days to Germination (DG)	0.99	5.53**	0.41
Days to first male flowering (DFMF)	1.56	6.06**	0.77
Days to first female flowering (DFFF)	10.43	8.17	3.48
Days to first harvest of fruits (DFH)	2.51	17.56**	1.25
Sex Ratio [M:F] (SR)	0.74	3.55**	0.37
Plant Height [30 DAS] (PH30)	19.53	2207.63**	80.47
Plant Height [60 DAS] (PH60)	66.54	3090.58**	200.71
Leaves per plant [30 DAS] (LPP30)	1.75	21.99**	3.16
Leaves per plant [60 DAS] (LPP60)	34.91	82.39**	22.74

Characters	Mean sum of Squares		
	Replication (df=2)	Treatment/ Genotypes (df=10)	Error (df=20)
Number of primary branches (NPB)	0.51	0.82**	0.14
Leaf length [cm] (LL)	0.06	8.21**	0.79
Leaf width [cm] (LW)	0.48	3.35**	0.97
Number of fruits per plant (NFPP)	0.01	5.87**	1.28
Fruit length [cm] (FL)	13.01	69.63**	4.36
Fruit girth [cm] (FG)	0.02	1.51**	0.16
Fruit weight [g] (FW)	3.06	286.43**	72.92
Fruit yield per plant [kg/plant] (FYPP)	0.01	0.33**	0.03
Fruit yield per hectare [t/ha] (FYPH)	18.12	415.64**	11.20
Number of seeds per fruit [avg] (NSPF)	14.16	29.17*	9.41
Vitamin C content [mg/100gm] (VCC)	0.03	0.39**	0.06
Shelf life [in days]	0.41	0.82**	0.11

** , * Significant at 1% and 5% level of significance respectively

3. RESULTS AND DISCUSSION

3.1 Analysis of Variance for 21 Characters Studied in Ridge Gourd Genotypes

The analysis of variance for all characters of ridge gourd genotypes (Table 3) revealed presence of good extent of significant differences among the genotypes for all traits. Henceforth, the data for all 21 characters that showed sufficient amount of significant differences were subjected to further statistical analysis. These results were in agreement with the studies conducted by Singh et al. [9], Choudhary and Kumar [10], Samadia [11], Rabbani et al. [12], Kumar et al. [13], Koppad et al. [14], Khan et al. [15], Bhargav et al. [16], Gautam and Balmohan [17], Divyaraj et al. [18], Akula and Topono [19] and Chinthalapudi et al. [20].

3.2 Genetic Variability

The Genotypic and Phenotypic coefficient of variation has been predicted in Table 4 and Fig. 1. Both high GCV and PCV was recorded for fruit yield per hectare followed by days to germination and plant height [30DAS] exhibited high estimates of GCV and PCV both. While Both Moderate GCV and PCV was recorded for plant height [60DAS], leaf length, fruit length, fruit girth, fruit yield per plant and shelf life in comparison to other characters indicating the presence of high amount of genetic variability for these characters. Similar results for high GCV and PCV were concluded earlier by was earlier reported by Singh et al. [9], Samadia [11], Rabbani et al. [12], Khan et al. [15], Ananthan and Krishnamoorthy [21] while, for moderate GCV and PCV was earlier inferred by Rabbani et

al. [12], Kumar et al. [13], Koppad et al. [14], Bhargav et al. [16], Manoj et al. [22], Ramesh et al. [23] and Kanan et al. (2019). This also suggests that improvement in these characters might be gained to a reasonable extent therefore, selection for these characters would be effective because response to selection is directly proportional to the variability present in the experimental material. In present study, heritability (broad sense) ranged from 30.99% for Days to first female flowering to 92.32% for Fruit yield per hectare.

3.3 Heritability and Genetic Advance

Genetic parameters revealed that high heritability (broad sense) estimates (60% and above) was observed for fruit yield per hectare, plant height [30DAS], fruit length, plant height [60DAS], days to first harvest of fruits, days to germination, leaf length, sex ratio, fruit girth, fruit yield per plant, days to first male flowering, shelf life, leaf per plant [30DAS], Vitamin C content and number of primary branches per plant (Table 4 and Fig. 1). Similar results for high heritability for fruit yield per hectare, plant height [30DAS], fruit length was reported earlier by Singh et al. [9], Rabbani et al. [12], Koppad et al. [14], Ananthan and Krishnamoorthy [21], Singh et al. [24] and Pushpendra et al. [25]. High heritability for plant height [30DAS], days to germination was concluded earlier by Kumar et al. [13], Harshitha et al. [26], Kanan et al. [27] and Akula and Topono [19]. Similar conclusion for high heritability for Days to first male flowering, sex ratio, fruit yield per plant and fruit girth was given by Divyaraj et al. [18] and Chinthalapudi et al. [20]. Shelf life, leaf per plant [30DAS], Vitamin C content also had high heritability and similar results was concluded by Bhargav et al. [16], Kartik et al. [28]

and Manoj et al. [22] in their work. Days to first female flowering, leaf per plant [60DAS], leaf width, number of seeds per fruit showed moderate heritability which was similarly earlier concluded by Choudhary and Kumar [10], Samadia [11], Ananthan and Krishnamoorthy [21], Singh et al. [24] and Ramesh et al. [23]. Moderate heritability was also observed for number of fruits per plant, fruit girth. Similar results were concluded by Singh et al. [9], Rabbani et al. [12] and Chinthalpudi et al. [20]. Therefore, these characters are predominantly governed by additive gene action and could be improved through individual plant selection owing to their high heritability values. High genetic advance (Table 4 and Fig. 1) was observed for plant height [60DAS], plant height [30DAS] and fruit yield per hectare. Moderate genetic advance was observed for fruit weight only. While all other characters i.e. fruit length, leaf per plant [60DAS], days to first harvest of fruits, leaf per plant [30DAS], number of seeds per fruit, leaf length, days to germination, days to first male flowering, number of fruits per plant, sex ratio, days to first female flowering, leaf width, fruit girth, shelf life, number of primary branches per plant, vitamin C content and fruit yield per plant had low estimates of genetic advance. Similar results were concluded by Rabbani et al. [12], Khan et al. [15], Pushpendra et al. [25], Ramesh et al. [23], Divyaraj et al. [18], Akula and Topno [19] and Chinthalpudi et al. [20]. The high or moderate value of genetic advance indicates additive gene action whereas low genetic advance value indicates non-additive gene action. Fruit yield per hectare, fruit yield per

plant, fruit girth, fruit length, leaf length, plant height [60DAS], plant height [30DAS] and days to germination exhibited high heritability broad sense coupled with high values for genetic advance as percent of mean. This indicates closeness of respective σ^2_p and σ^2_g value thereby low environmental effect on expression of these characters. Such values may be attributed to the additive gene effects and direct selection for these traits would be fruitful. This indicated that priority should be given to these characters during selection for improvement in ridge gourd. High heritability coupled with moderate genetic advance as percent of mean was observed for leaf per plant [30DAS], number of primary branches, Vitamin C content and Shelf life. While moderate heritability coupled with moderate genetic advance as percent of mean was recorded for leaf per plant [60DAS], number of fruits per plant and fruit girth. This also pointed out the fact that these characters have appreciable genetic potential and are comparably less influenced by environment, hence desirable for simple selection in breeding programmes. High to moderate heritability coupled with low genetic advance as percent of mean was recorded for rest of the characters which indicated that these characters are highly influenced by environmental effects and selection would be ineffective. Similar inferences were drawn by Singh et al. [9], Choudhary and Kumar [10], Samadia [11], Rabbani et al. [12], Kumar et al. [13], Varalakshmi et al. (2015), Khan et al. [15], Pushpendra et al. [25], Ramesh et al. [23], Divyaraj et al. [18], Akula and Topno [19] and Chinthalpudi et al. [20].

Table 4. Range, variability and genetic parameters for 21 quantitative characters of 11 Ridge gourd genotypes

Sl. No	Characters	Range		Variability		Genetic Parameters		
		Minimum	Maximum	GCV (%)	PCV (%)	h ² (Heritability Broad Sense) (%)	GA (5% LOS)	GA as % Mean
1	Days to Germination (DG)	4.00	7.67	22.39	24.96	80.49	2.41	41.39
2	Days to first male flowering (DFMF)	34.66	39.58	3.53	4.24	69.38	2.27	6.06
3	Days to first female flowering (DFFF)	44.17	50.25	2.73	4.91	30.99	1.43	3.13
4	Days to first harvest of fruits (DFH)	59.67	68.09	3.79	4.20	81.26	4.33	7.04
5	Sex Ratio [M:F] (SR)	20.78	24.13	4.73	5.50	74.01	1.82	8.38
6	Plant Height [30 DAS] (PH30)	84.84	175.83	20.80	21.95	89.80	51.98	40.61

Sl. No	Characters	Range		Variability		Genetic Parameters		
		Minimum	Maximum	GCV (%)	PCV (%)	h ² (Heritability Broad Sense) (%)	GA (5% LOS)	GA as % Mean
7	Plant Height [60 DAS] (PH60)	156.92	258.25	14.04	15.43	82.16	58.16	26.31
8	Leaves per plant [30 DAS] (LPP30)	22.42	30.08	9.56	11.73	66.46	4.20	16.07
9	Leaves per plant [60 DAS] (LPP60)	42.42	61.00	8.41	12.31	46.64	6.27	11.83
10	Number of primary branches (NPB)	4.17	6.08	9.80	12.64	60.08	0.75	15.65
11	Leaf length [cm] (LL)	7.98	13.99	15.59	17.91	75.77	2.82	27.96
12	Leaf width [cm] (LW)	11.56	14.67	6.75	10.09	44.79	1.22	9.31
13	Number of fruits per plant (NFPP)	14.42	18.75	7.64	10.37	54.28	1.87	11.59
14	Fruit length [cm] (FL)	21.35	35.14	16.03	17.86	83.27	8.76	30.65
15	Fruit girth [cm] (FG)	4.26	6.42	13.25	15.48	73.28	1.18	23.38
16	Fruit weight [g] (FW)	94.00	121.38	8.01	11.39	49.39	12.21	11.59
17	Fruit yield per plant [kg/plant] (FYPP)	1.54	2.61	14.43	17.01	71.95	0.55	25.22
18	Fruit yield per hectare [t/ha] (FYPH)	25.39	61.91	27.40	28.52	92.32	22.98	54.24
19	Number of seeds per fruit [avg] (NSPF)	31.71	40.69	7.03	10.96	41.16	3.39	9.29
20	Vitamin C content [mg/100gm] (VCC)	2.93	4.30	8.87	11.00	65.07	0.55	14.74
21	Shelf life [in days]	3.33	5.00	11.30	13.85	66.61	0.81	19.01




Fig. 1. Histogram representing the relationship among the GCV, PCV, heritability, genetic advance and genetic advance as percent of mean in ridge gourd

4. CONCLUSION

From the present investigation it is concluded that among 11 genotypes of ridge gourd on the basis of mean performance 3 genotypes namely; Dharidar, Anamika and Jaipur long had substantially higher yield and performed better for other desirable traits as compared to Pusa Nasdar (Check). Genetic parameters also revealed that high heritability (broad sense) was observed for fruit yield per hectare, plant height [30DAS], fruit length, plant height [60DAS], days to first harvest of fruits, days to germination, leaf length, sex ratio, fruit girth, fruit yield per plant, days to first male flowering, shelf life, leaf per plant [30DAS], Vitamin C content and number of primary branches per plant. Fruit yield per hectare, fruit yield per plant, fruit girth, fruit length, leaf length, plant height [60DAS], plant height [30DAS] and days to germination exhibited high heritability broad sense coupled with high values for genetic advance as percent of mean. This indicated that priority should be given to these characters during selection for improvement in ridge gourd.

ACKNOWLEDGEMENT

The author would like express heartfelt gratitude to Dr. Devi Singh (Associate Professor, Department of Horticulture, NAI, SHUATS, Prayagraj for his continuous guidance and supervision throughout our research period. And also, equally extend our profound gratitude to Dr. Vikram Singh, Associate Professor, Directorate of Seed and Farm, SHUATS, Prayagraj for his valuable suggestions, guidance.

COMPETING INTERESTS

Authors have declared that no competing interests exist.

REFERENCES

- McKay JW. Chromosome numbers in the Cucurbitaceae. Botanical Gazette. Botanical Gazette. 1930;89(4):416-7. DOI: 10.1086/334075.
- De Candolle A. Origin of cultivated plants. New York: Hafner Publication Co.; 1967, (Reprint of 2nd edition); 1959.
- National Horticultural Board. Ministry of Agriculture & farmers welfare (DAC & FW). Government of India, 2019-20; 2019-20.
- Khan M, Khalid N, Khan A, Mohammad SB. Genetic variability and correlation studies in mungbean. J Biol Sci. 2005;1(3):117-9.
- Fisher RA, Yates F. Statistical tables for biological, agricultural and medical research. Vol. 143. London: Oliver & Boyd; 1963.
- Burton GW, Devane EM. Estimation of heritability in tall fescue (*Festuca arundinacea*) from replicated clonal material. Agron J. 1952;45:478-80.
- Allard RW. Relationship between Relationship between genetic diversity and consistency of performance in different environment. Crop Sci. 1960;1:127-32.
- Johnson HW, Robinson HF, Comstock RE. Estimate of genetic and environmental variability in soyabean. Agron J. 1955;47(7):314-8. DOI: 10.2134/agronj1955.00021962004700070009x.
- Singh RP, Mohan J, Singh D. Studies on genetic variability and heritability in ridge gourd (*Luffa acutangula* L.). Agric Sci Dig. 2002;22(4):79-80.
- Choudhary BR, Kumar S. Genetic analysis in ridge gourd (*Luffa acutangula* Roxb. L.) under hot arid conditions. Indian J Arid Hortic. 2011;6(2):55-8.
- Samadia DK. Genetic variability studies in ridge gourd (*Luffa acutangula* L.) under arid environment. Indian J Hortic. 2011;68(2):275-7.
- Rabbani MG, Naher MJ, Hoque S. Variability, character association and diversity analysis of ridge gourd (*Luffa acutangula* roxb.) genotypes of Bangladesh. SAARC J Agric. 2012;10(2):1-10. DOI: 10.3329/sja.v10i2.18319.
- Kumar R, Ameta, KD, Dubey RB, Pareek S. Genetic variability, correlation and path analysis in sponge gourd (*Luffa cylindrica* Roem.). Afr J Biotechnol. 2013;12(6):539-43.
- Koppad SB, Chavan ML, Hallur RH, Rathod V, Shantappa T. Variability and character association studies in ridge gourd (*Luffa acutangula* Roxb.) with reference to yield attributes. J Glob Biosci. 2015;4(6):2332-42.
- Khan ASMR, Rabeya E, Rashid MH, Sheikh I, Chaki AK. Variability, heritability, character association, path analysis and morphological diversity in ridge gourd. Agric Nat Resour. 2016;50(2):483-9.

16. Bhargava AK, Singh VB, Kumar P, Meena RK. Efficiency of selection based on genetic variability in Ridge gourd [*Luffa acutangula* L. (Roxb.)]. J Pharmacogn Phytochem. 2017;6(4):1651-5.
17. S.p. GS, T.n. B. Genetic variability studies in F₂ and F₃ generations of ridge gourd for yield and yield components [*Luffa acutangula* (L.) Roxb.]. Ann Plant Sci. 2018;7(8):2385-90. DOI: 10.21746/aps.2018.7.8.3.
18. Divyaraj S, Prasad VM, Topno SE, Shabi M, Madhukar V. Study on genetic variability, heritability, character association and genetic divergence in ridge gourd (*Luffa acutangula* (L.) Roxb.). Int J Chem Stud. 2019;7(4):976-9.
19. Akula S, Topno SE. Genetic variability, heritability and divergence in ridge gourd (*Luffa acutangula* L. Roxb.). Green Farming. 2020;11(4):314-8.
20. Chinthalapudi DPM, Kranthi RG, Usha KK, Uma JK, Narasimharao S. Variability studies in F₃ population of ridge gourd (*Luffa acutangula*) for yield and yield attributing traits. The Pharm Innov J. 2021;10(7):612-5.
21. Ananthan M, Krishnamoorthy V. Genetic variability, correlation and path analysis in ridge gourd (*Luffa acutangula* (Roxb) L.). Int J Curr Microbiol Appl Sci. 2017;6(6):3022-6. DOI: 10.20546/ijcmas.2017.606.359.
22. Manoj YB, Lakshmana D, Ganapathi M, Chandana BC. Studies on character association and genetic variability for important traits in ridge gourd (*Luffa acutangula* L.). Green Farming. 2018;9(2):244-7.
23. Ramesh ND, Praveen C, Radhelal D, Pushpa SG, Priyanka PL. Study on genetic variability, heritability and genetic advance in ridge gourd (*Luffa acutangula* (L.) Roxb.). Int J Chem Stud. 2018;6(4):1329-33.
24. Singh V, Rana DK, Shah KN. Genetic variability, heritability and genetic advance in some strains of bitter gourd (*Momordica charantia* L.) under subtropical conditions of Garhwal Himalaya. Plant Arch. 2017;17(1):564-56.
25. Pushpendra K, Singh MK. Genetic variability, heritability and genetic advance study in ridge gourd [*Luffa acutangula* L. (Roxb.)] germplasm. Int J Res Anal Rev. 2018;5(4):13-8.
26. Harshitha S, Meenakshi S, Indiresk KM. Variability and heritability studies for horticultural traits in ridge gourd [*Luffa acutangula* (L.) Roxb.]. Int J Bio-Resource Stress Manag. 2019;1(4):335-9.
27. Kannan A, Rajamanickam C, Krishnamoorthy V, Arunachalam P. Genetic variability, correlation and path analysis in f₄ generation of ridge gourd (*Luffa acutangula* (Roxb.) L.). Int J Chem Stud. 2019;7(3):208-13.
28. Karthik K, Varalakshmi B, Kumar G, Lakshmi N. Genetic variability studies of ridge gourd advanced inbred lines (*Luffa acutangula* (L.) Roxb.). Int J Pure App Biosci. 2017;5(6):1223-8. DOI: 10.18782/2320-7051.6079.

© 2022 Yadav and Singh; This is an Open Access article distributed under the terms of the Creative Commons Attribution License (<http://creativecommons.org/licenses/by/4.0>), which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Peer-review history:
The peer review history for this paper can be accessed here:
<https://www.sdiarticle5.com/review-history/89913>